PRATIKSHA TECHNOLOGIES, PALGHAR				
Address :- Plot No. J-4, Gate No. 2, M.I.D.C, Tarapur Industrial Estate, Boisar - 401506				
Contact - 7276586591, 7020755992 , Mail - sales@pratikshatechnologies.com				
GST No. 27CSRPP6644L1ZR				
Client				
Project	400A MCC Panel		14 April 2026	
Ref No.	PT-004		Revision - R00	
	Kind Attn:-			
	Please find below offer for 400A MCC Panel.			
Sr. No.	**Description**	**Make**	**Model**	**Qty**
1	SFU, 400A, TPN with Fuse	L&T		1
2	Aux. Contact 1No + 1NC	Standard		1
3	Indication Lamp, R, Y, B, G, A	Standard		5
4	MCB 6A SP	L&T		4
5	Cable, 1.5sqmm	Polycab		15
6	Cable, 2.5sqmm	Polycab		15
7	Connector, 2.5sqmm	Connectwell		15
8	Neutral Link, 32A	Standard		2
	63A SFU Feeder			**2**
1	SFU, 63A, TPN with Fuse	L&T		2
2	Connector, 35sqmm	L&T		8
3	Cable, 16sqmm	L&T		10
	10 HP S/D			**2**
1	SFU, 63A, TPN with Fuse	L&T		2
2	HRC Fuse, 20A	L&T		6
2	Aux. Contact 1No + 1Nc	L&T		2
3	Indication Lamp, Red	TNI		4
4	Indication Lamp, Green	L&T		4
5	Indication Lamp, Amber	L&T		2
6	Contactor, 25A	L&T		6
7	Aux. Contact 2No + 2Nc	L&T		6
8	MPD	Excel		2
9	Star Delta Timer	Selec		2
10	6A, 2P, Auto/Manual Switch	Salzer		2
11	Head Push Button, Red & Green with 1No+1NC	TNI		4
12	Power Cable 2.5 Sqmm	Polycab		30
13	Control Cable 1.5 Sqmm	Polycab		30
14	Power Connector 4 Sqmm	Connectwell		30
15	Control Connector 2.5 Sqmm	Connectwell		30
	12.5 HP S/D			**2**
1	SFU, 63A, TPN with Fuse	L&T		2
2	HRC Fuse, 32A	L&T		6
2	Aux. Contact 1No + 1Nc	L&T		2
3	Indication Lamp, Red	TNI		4
4	Indication Lamp, Green	L&T		4
5	Indication Lamp, Amber	L&T		2
6	Contactor, 25A	L&T		6
7	Aux. Contact 2No + 2Nc	L&T		6
8	MPD	Excel		2
9	Star Delta Timer	Selec		2

10	6A, 2P, Auto/Manual Switch	Salzer		2
11	Head Push Button, Red & Green with 1No+1NC	TNI		4
12	Power Cable 2.5 Sqmm	Polycab		20
13	Control Cable 1.5 Sqmm	Polycab		20
14	Power Connector 10 Sqmm	Connectwell		20
15	Control Connector 2.5 Sqmm	Connectwell		30
16	Cable, 6sqmm	Polycab		20
	15 HP S/D			**1**
1	SFU, 63A, TPN with Fuse	L&T		1
2	HRC Fuse, 32A	L&T		3
2	Aux. Contact 1No + 1Nc	L&T		1
3	Indication Lamp, Red	TNI		2
4	Indication Lamp, Green	L&T		2
5	Indication Lamp, Amber	L&T		1
6	Contactor, 25A	L&T		3
7	Aux. Contact 2No + 2Nc	L&T		3
8	MPD	Excel		1
9	Star Delta Timer	Selec		3
10	6A, 2P, Auto/Manual Switch	Salzer		3
11	Head Push Button, Red & Green with 1No+1NC	TNI		2
12	Power Cable 2.5 Sqmm	Polycab		10
13	Control Cable 1.5 Sqmm	Polycab		10
14	Power Connector 10 Sqmm	Connectwell		10
15	Control Connector 2.5 Sqmm	Connectwell		10
16	Cable, 6sqmm	Polycab		10
	20 HP S/D			**2**
1	SFU, 63A, TPN with Fuse	L&T		2
2	HRC Fuse, 40A	L&T		6
2	Aux. Contact 1No + 1Nc	L&T		2
3	Indication Lamp, Red	TNI		4
4	Indication Lamp, Green	L&T		4
5	Indication Lamp, Amber	L&T		2
6	Contactor, 25A	L&T		6
7	Aux. Contact 2No + 2Nc	L&T		6
8	MPD	Excel		2
9	Star Delta Timer	Selec		2
10	6A, 2P, Auto/Manual Switch	Salzer		2
11	Head Push Button, Red & Green with 1No+1NC	TNI		4
12	Power Cable 2.5 Sqmm	Polycab		20
13	Control Cable 1.5 Sqmm	Polycab		20
14	Power Connector 10 Sqmm	Connectwell		20
15	Control Connector 2.5 Sqmm	Connectwell		20
16	Cable, 6sqmm	Polycab		20
	4 HP DOL			**1**
1	SFU, 32A, TPN with Fuse	L&T		1
2	HRC Fuse, 16A	L&T		3
2	Aux. Contact 1No + 1Nc	L&T		1
3	Indication Lamp, Red	L&T		2
4	Indication Lamp, Green	L&T		2
5	Indication Lamp, Amber	L&T		1
6	Contactor, 18A	L&T		1

7	Aux. Contact 2No + 2Nc	L&T		1
8	MPD	Excel		1
9	6A, 2P, Auto/Manual Switch	Salzer		1
10	Head Push Button, Red & Green with 1No+1NC	TNI		2
11	Power Cable 2.5 Sqmm	Polycab		15
12	Control Cable 1.5 Sqmm	Polycab		15
13	Power Connector 4 Sqmm	Connectwell		15
14	Control Connector 2.5 Sqmm	Connectwell		15
	3 HP DOL			**5**
1	SFU, 32A, TPN with Fuse	L&T		5
2	HRC Fuse, 16A	L&T		15
2	Aux. Contact 1No + 1Nc	L&T		5
3	Indication Lamp, Red	L&T		10
4	Indication Lamp, Green	L&T		10
5	Indication Lamp, Amber	L&T		5
6	Contactor, 18A	L&T		5
7	Aux. Contact 2No + 2Nc	L&T		5
8	MPD	Excel		5
9	6A, 2P, Auto/Manual Switch	Salzer		5
10	Head Push Button, Red & Green with 1No+1NC	TNI		10
11	Power Cable 2.5 Sqmm	Polycab		75
12	Control Cable 1.5 Sqmm	Polycab		75
13	Power Connector 4 Sqmm	Connectwell		75
14	Control Connector 2.5 Sqmm	Connectwell		75
	2 HP DOL			**2**
1	SFU, 32A, TPN with Fuse	L&T		2
2	HRC Fuse, 10A	L&T		6
3	Aux. Contact 1No + 1Nc	L&T		2
4	Indication Lamp, Red	L&T		4
5	Indication Lamp, Green	L&T		4
6	Indication Lamp, Amber	L&T		2
7	Contactor, 18A	L&T		2
8	Aux. Contact 2No + 2Nc	L&T		2
9	MPD	Excel		2
10	6A, 2P, Auto/Manual Switch	Salzer		2
11	Head Push Button, Red & Green with 1No+1NC	TNI		4
12	Power Cable 2.5 Sqmm	Polycab		30
13	Control Cable 1.5 Sqmm	Polycab		30
14	Power Connector 4 Sqmm	Connectwell		30
15	Control Connector 2.5 Sqmm	Connectwell		30
	Copper Busbar			
1	40X10X1800	Standard		1
2	40X10X3300	Standard		1
3	40X5X1800	Standard		1
4	40X5X3300	Standard		1
	Common Utility			
1	Din Rail	Standard	-	1
2	PVC Duct	Rolly Tray	-	1
	Enclosure			
1	MS Panel, 2100 (H) X 3300 (H) X 350 (D) in MM. Panel Body: 2mm, Doors: 1.6, Partition: 1.2 in MM	Fabricated	-	1

	OTHERS :-			
1	Electrical Hardware, Lug, Duct, Rail	VSPS	-	1
2	Labor Charges	VSPS	-	1
	OFFER COST :- 6,75,900/- Plus GST			
	TERMS & CONDITION :-			
	1. GST - Extra 18% at present			
	2. Packing & Forwarding - Extra or Customer Scope			
	VSPS Standard - Bubal Packing as Standard			
	3. Transportation - Extra or Customer Scope			
	4. Delivery Period - 3-4 Weeks from date of Drawing approval . VFD & PLC -Based on availibility stock			
	5. Insurnce - Extra or Customer Scope			
	6. Payment Terms - 50% Advance , Balance against material			
	7. Commissioning & Installation - Extra per day basis			
	PLC ENGINEER			
	ELECTRICAL ENGINEEER			
	ELECTRICAN			
	8. Loadging & Boarding - Extra at Actual or Customer Scope			
	9. Traveling & Transport - Extra at Actual or Customer Scope			
	10. Offer Validity - 2 Weeks from offer date			